

15095205700000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Kingman County, Sec. 20 Twp. 28 Rge. 5 (X) (W)

Location as "NE/CNW/SW" or footage from lines C NE/4

Lease Owner Graves Drilling Co., Inc.

Lease Name Robinson Well No. 1

Office Address 910 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 15 May 1977

Application for plugging filed May 15 1977

Application for plugging approved May 15 1977

Plugging commenced May 15 1977

Plugging completed May 15 1977

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin

Producing formation Depth to top Bottom Total Depth of Well 3925 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 240 feet. Followed by wooden plug and 1/2 sack hulls. Placed 35 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 12 sacks cement to base of well cellar. Plugged rat hole with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 910 Union Center, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss. John C. Graves

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves 910 Union Center, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May 1977

Courtney M. Graves Notary Public.
MAY 31 1977

My commission expires: 2 February 1980



CONSERVATION DIVISION
Wichita, Kansas

15-095-20570-0000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: 9 May 1977
 910 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: 15 May 1977
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 213' of used 8 5/8" LOCATION: Robinson No. 1
 cemented with 170 sacks C NE/4
 Section 20-28S-5W
 Kingman County, Kansas

0 - 213 Red bed
 213 - 798 Red bed & shale
 798 - 1415 Shale & lime
 1415 - 2220 Lime & shale
 2220 - 2464 Shale & lime
 2464 - 2600 Lime
 2600 - 3049 Shale & lime
 3049 - 3217 Lime & shale
 3217 - 3415 Shale & lime
 3415 - 3871 Lime & shale
 3871 - 3925 Lime
 3925 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John Graves*
President

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 27th day of May, 1977

My commission expires: 2 February 1980

Courtney M. Graves
Courtney M. Graves Notary Public



RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1977

CONSERVATION DIVISION
Wichita, Kansas