

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-01060-0000

LEASE NAME Bolinger A #3

WELL NUMBER _____

SPOT LOCATION 330' FNL, 2310' FEL
NE 1/4

SEC. 21 TWP. 28 RGE. 5w(E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 6/26/85

Plugging Completed 7/1/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing bought f/ Cities Service

ADDRESS Box 347, Chase, Ks. 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3837'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	208'	none
				5 1/2"	3803'	2386'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 1 hull, & 100 sacks 60/40 poz 2% gel 3% c.c. Shot pipe at 2500' & 2386'. Pulled 75 joints of pipe. Plugged well with 3 hulls, 15 gel, and 100 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice

RECEIVED
STATE CORPORATION COMMISSION


R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1985

My Commission expires:



Notary Public


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-095-01060000

Company- CITIES SERVICE OIL CO.
Farm- Bolinger No. 3

SEC. 21 T. 28 R. 5W
NW NW NE
330' S 330' E of N/4c
County Kingman
KANSAS

Total Depth. 3837
Comm. 11-18-52 Comp. 12-19-52
Shot or Treated.
Contractor. Braden Drilling Co.
Issued. 6-13-53



CASING:

8 5/8 set at 208' w/ 125 sx cement
5 1/2 set at 3803' w/ 150 sx cement

Elevation. 1388 RB

Production Flowed 135 BO 4 BW

Figures Indicate Bottom of Formations.

sand	40
red bed	208
red bed, shale & shells	635
shale & shells	895
lime	1500
shale & shells	1575
shale & lime	2775
lime	3785
Mississippi chert	3837
Total Depth	

TOPS:	
Brown lime	2991
Lansing	3002
Base KC	3464
Mississippi chert	3782

SHOW	
NSO	2991
SSO	3352-67
SO	3384-86
SO	3390-3410
NSO	3782-3806
SSO	3806-15
SO	3818-22
SO	3822-27
SSO	3827-37
Best pay	3806-27

Cleaned out to RTD & filled hole w/
2300' water.
Sw bd. 5 BO thru tubing while swbing
water load
Flowed 9 Bo in 1/2 hr. (28/64" choke
890" on csg. 220" on tubing) (Csg
press. dropped to 390" & tubing
press. increased to 240") Flowed by
heads 14 BO, no water in 24 hrs.

Flowed 48 BO, 5% water, 24 hrs.

RECEIVED
STATE CORPORATION COMMISSION

APR 09 1985

CONSERVATION DIVISION
Wichita, Kansas