

RECEIVED
STATE CORPORATION COMMISSION

15-09501062-000

JUL 16 1974

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Kingman County, Sec. 21 Twp. 28S Rge. 5 W (E) (W)

Location as "NE/CNW&SW" or footage from lines NW SE NW

Lease Owner Icor Addis

Lease Name Broadway Well No. 3

Office Address 5307 E. Central, Wichita, Kansas 67208

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 12-29 19 50

Application for plugging filed 6-26 19 74

Application for plugging approved 6-27 19 74


Plugging commenced 7-9 19 74

Plugging completed 7-12 19 74

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation Depth to top Bottom Total Depth of Well 3820'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3433'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3820' to 3800'. Dumped 5 ax of cement. Mudded hole 250'. Made 10' of rock bridge. Dumped 25 ax of cem. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 ax of cement, filling to the bottom of the celler.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

2809 King St. Hutchinson, Kansas 67501

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 1974.

My commission expires December 31, 1977

[Signature] Notary Public.

15-095-01062-0000

W

Broadway #3
Owner: Earl F. Wakefield
Contractor: Earl F. Wakefield
Comm: 12-16-50 Comp: 12-29-50

NW SE NW 21-28S-5W
Kingman County, Kansas
Casing: 127' of 8 5/8"
387.89' of 5 1/2" w/50 sax
387'

Elevation 1381 DF

Surface	140
Shale & Shells	355
Shale, Shells & Salt	845
Shale & Shells	1020
Shale & Lime Streaks	1165
Lime & Shale	1550
Shale & Shells	1720
Shale & Lime	3300
Lime	3307
Lime & Shale	3390
Lime	3450
Shale & Lime	3797
Lime & Chert	3820
T. D.	3820

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1974
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss

I hereby certify that the above is a true and correct copy of the log of the Broadway #3 well located NW SE NW, 21-28S-5W, Kingman County, Kansas.

Subscribed and sworn to before me this _____ day of _____, 1951.

My Commission Expires: 12-23-54