

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Kingman County. Sec. 21 Twp. 28 Rge. (E) 5 (W)

Location as "NE/CNW*SW*" or footage from lines NW SE SE

Lease Owner Earl F. Wakefield

Lease Name R. Dewey Well No. 1

Office Address 307 Union Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed March 8, 19 52

Application for plugging filed December 16, 19 53

Application for plugging approved December 16, 19 53

Plugging commenced December 17, 19 53

Plugging completed December 21, 19 53

Reason for abandonment of well or producing formation Production too small to operate equitably

If a producing well is abandoned, date of last production June, 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3842 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	108.55'	None
				7	3903.75	3270

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3842 feet to 3810 feet and cemented with six sacks. Filled hole with mud to surface, Set bridge at 200 feet and cemented with 25 sacks. Filled hole with mud to surface again and put a cement cap on with 5 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield

Address _____

STATE OF Kansas COUNTY OF Sedgwick, ss.

Earl F. Wakefield

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
307 Union Nat'l Bank Bldg.
Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 54

My Commission Expires Apr. 18, 1955

Henry D. Ficken

Notary Public.

My commission expires _____

PLUGGING
FILED SEC 21 T 28 R 50
BOOK PAGE 149 LINE 40

24-7388-5 3-93-20M

01-11-54

15-095-01741-0500

R. Dewey #1
Owner: Earl F. Wakefield
Contractor: Earl F. Wakefield
Comm: 8-12-51 Comp: 8-30-51

NW SE SE 21-28-5W
Kingman County, Kansas
Casing: 103' of 10 3/4"
3878.20' of 7"

Elevation: 1373

Surface	65
Hard Cement	100
Shale & Red Rock	155
Shale & Lime Streaks	160
Shale & Shells	340
Shale & Salt Streaks	565
Shale & Salt	890
Shale, Salt & Shells	1065
Lime & Shale	2240
Shale & Lime	2380
Lime & Shale	2425
Lime	2445
Lime & Shale	2575
Shale & Lime	2680
Lime & Shale	3285
Lime	3315
Lime & Shale	3480
Lime	3513
Lime & Shale	3675
Shale & Lime	3780
Chert	3805
Chert & Lime	3823
Cherty Lime	3885
Total Depth	3885

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the R. Dewey #1 well located NW SE SE 21-28-5W, Kingman County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 4th day of September, 1951.

Edgar J. Gaffney

My Commission Expires: 12-23-54

PLUGGING
FILE SEC 21 T 28 R 3W
BOOK PAGE 149 LINE 40