


15095-00267000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 23 Twp. 28 Rge. (E) 5 (W)
Location as "NE/CNW%SW%" or footage from lines NE SE NW
Lease Owner Shawver-Armour, Inc.
Lease Name Turner Well No. 1
Office Address 817 Central Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-3-57 19
Application for plugging filed 5-3-57 19
Application for plugging approved 5-3-57 19
Plugging commenced 5-3-57 19
Plugging completed 5-3-57 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 4376 Bottom 4391 Total Depth of Well 4391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-----|-------|--------|------------|
| Surface | Water | 0 | 168 | 8 5/8 | 168 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4391 - 250 Fill w/heavy mud
250 - 120 Set Halliburton Plug then 1/2 sax hulls then 30 sax cement thru drill pipe
120 - 35 Fill w/heavy mud
35 - 0 Set Halliburton Plug then 1/2 sax hulls then 10 sax cement to botton go cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver-Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

James Armour (owner or operator) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour James Armour
817 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 57

Marjorie Hall
Marjorie Hall Notary Public.

My commission expires December

FILED
STATE CORPORATION COMMISSION
MAY 10 1957
WICHITA, KANSAS
05-10-57

PLUGGING
FILE SEC. 23 T. 28 R. 5W
BOOK PAGE 11 LINE 17

15-095-00267-0000

DRILLING LOG

COMPANY: SHAWVER-ARMOUR, INC. LOCATION: NE SE NW
 CONTRACTOR: SHAWVER-ARMOUR, INC. 23-28S-5W
 Kingman County
 FARM NAME: TURNER # 1 ELEVATION: 1381 KB
 COMMENCE: April 15, 1957
 COMPLETED: May 2, 1957

CASING RECORD

164' 8 5/8" w/125 sx 2% cc

| FORMATION | TO | | |
|-------------------------|----------|--------------------|------|
| Shale & Red Bed | 40 | TOPS | |
| Red Rock & Lime Shells | 164 | Lansing | 3052 |
| Red Bed & Shale | 220 | Kansas City | 3220 |
| Sandy Shale & Shells | 720 | Base Kansas City | 3458 |
| Shale & Salt | 768 | Mississippi | 3840 |
| Anhydrite | 825 | Kinderhook | 4125 |
| Anhydrite & Shale Strks | 910 | Viola | 4250 |
| Shale & Lime | 1130 | Simpson | 4260 |
| Shale & Lime Strks | 1325 | Arbuckle | 4375 |
| Lime & Shale | 3065 | Rotary Total Depth | 4391 |
| Lime Shale & Sand | 3120 | | |
| Shale & Lime | 3260 | | |
| Lime | 3496 | | |
| Lime & Shale | 3835 | | |
| Lime | 3910 | | |
| Chert & Lime | 3976 | | |
| Lime | 4005 | | |
| Lime & Shale | 4089 | | |
| Lime | 4126 | | |
| Shale & Lime | 4250 | | |
| Lime | 4263 | | |
| Shale & Sand | 4365 | | |
| Shale & Lime | 4376 | | |
| Lime | 4391 RTD | | |

STATE OF KANSAS)
) SS
 SEDGWICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drill reports.

SHAWVER-ARMOUR, INC.

By: James Armour
 James Armour, Sec. Treas.

Subscribed and sworn to before me this 9th of May 1957

Marjorie Hall
 Marjorie Hall, Notary Public

My Commission expires December 29, 1959.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 10 1957
 CONSERVATION DIVISION
 WICHITA, KANSAS

PLUGGING
 FILE SEC. 23 T. 28 R. 5W
 BOOK PAGE 11 LINE 17