

15-095-20543-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 17 Twp. 28S Rge. 5 NE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SW SE NW

Lease Owner Graves Drilling Co., Inc.

Lease Name Krase Well No. 1

Office Address 910 Union Center, Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed November 26, 1976

Application for plugging filed November 26, 1976

Application for plugging approved November 26, 1976

Plugging commenced November 26, 1976

Plugging completed November 26, 1976

Reason for abandonment of well or producing formation


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 225 feet. Followed by wooden plug and 1/2 sack hulls. Placed 35 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 15 sacks cement to base of well cell. Plugged rat hole with 5 sacks cement.

11-30-76

NOV 30 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.

Betty Brandt (employee of owner) or (operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Betty Brandt
910 Union Center, Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 29th day of November 1976

My commission expires February 2, 1980

Courtney M. Graves
Courtney M. Graves Notary Public



ROTARY DRILLERS' LOG

15-095-20543-0000

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: 19 Nov. 1976

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: 25 Nov. 1976

CASING RECORD: 5 Jts. 213' of used 8-5/8"
cemented with 180 sacks

LOCATION: Krase No. 1
SW SE NW
17-28S-5W
Kingman County, Kansas

0 - 213 Red bed
 213 - 1270 Shale & shells
 1270 - 1485 Lime & shale
 1485 - 1732 Shale & lime
 1732 - 3285 Shale
 3285 - 3598 Shale & lime
 3598 - 3718 Lime
 3718 - 3740 Lime & shale
 3740 - 3907 Lime
 3907 Rotary Total Depth

RECEIVED
 NOV 30 1976
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Betty Brandt
Secretary-Treasurer

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 29th day of November, 1976

My commission expires: 2 February 1980

Courtney M. Graves
Courtney M. Graves Notary Public

