

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21527-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 20-32S-20W
1729 feet from S Section Line, 2987 feet from E Section Line
Lease Name: HERD A Well #: 1
County: COMANCHE Total Vertical Depth: 5250 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
CIBP		5100		
PROD	5.5	5224	3080	WITH 125 SX CMT
SURF	8.625	645		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/13/2016 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4550' WITH 2 SX CMT. PLUG AT 910' WITH 12 SX GEL & 50 SX CMT. PLUG AT 675' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2016 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4550' WITH 2 SX CMT. 1ST PLUG AT 920' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 680' WITH 50 SX CMT. 3RD PLUG AT 320' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5142	5146		MORROW SAND

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED
APR 15 2016
KCC DODGE CITY

Signed [Signature]
KCC WICHITA (TECHNICIAN)
APR 25 2016
RECEIVED

20
5-6-16