

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21063-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 25-31S-2E
2133 feet from S Section Line, 2195 feet from E Section Line
Lease Name: N R NELSON Well #: 2
County: SUMNER Total Vertical Depth: 1850 feet

Operator License No.: 7186
Op Name: DOCKING DEVELOPMENT COMPANY,
Address: PO BOX 928
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	1850		150 SX
SURF	8.625	220		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2016 12:00 PM
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.
Proposal Rcvd. from: LARRY BARTELSON Company: CANAAN WELL SERVICE, INC. Phone: (620) 968-7447

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 03/24/2016 10:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 1600'. RAN IN WITH 2 3/8" TUBING TO 1619' AND SPOT 25 SX OF 60/40 POS MIX W/4% GEL AND 3% CC W/ HULLS FOR BOTTOM PLUG, THEN RAN IN WITH WIRE LINE AND TAGGED TOP OF BOTTOM PLUG AT 1410'. THEN MIXED 115 SX OF 60/40 POS MIX W/ 4% GEL AND 1 1/2% CC W/HULLS @ 300' AND CIRCUALTED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
1668	1672		

Remarks: CONSOLIDATED CEMENTING OUT OF EL DORADO KS. TICKET #51198

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 26 2016

CONSERVATION DIVISION
WICHITA, KS

no
5-6-16

Form CP-2/3