

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20654-00-02
Spot: NWSENE SW Sec/Twnshp/Rge: 27-29S-39W
1969 feet from S Section Line, 3276 feet from E Section Line
Lease Name: JULIAN Well #: 1-27
County: STANTON Total Vertical Depth: 5800 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3975		WITH 2 SX CMT
CIBP		4143		
MSCC		3093		
PROD	4.5	5800	1826	WITH 200 SX CMT
SURF	8.625	1718		WITH 750 SX CMT

Well Type: SWD UIC Docket No: D27762.0 Date/Time to Plug: 04/07/2016 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: LARRY ROME Company: LONE STAR SERVICES. Phone: (303) 825-8956

Proposed Plugging Method: CIBP @ 4000' WITH 2 SX CMT. PLUG AT 1750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2016 12:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 3975' WITH 2 SX CMT. 1ST PLUG AT 1750' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.,

Perfs:

Top	Bot	Thru	Comments
4088	4122		
4044	4122		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED
APR 21 2016
KCC DODGE CITY

Signed [Signature]
KCC WICHITA JA (TECHNICIAN)
MAY 02 2016
RECEIVED

NO
5-6-16
cc uic
Form CP-2/3