

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21576-00-00
Spot: NENESW Sec/Twnshp/Rge: 2-21S-9W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: STEVENSON OWWO Well #: 1
County: RICE Total Vertical Depth: 3406 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3275		
PROD	4.5	3405		175 SX
SURF	8.625	248		175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/14/2016 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERLE Company: DAMAR RESOURCES Phone: (785) 623-3221

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2016 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING - CK BOTTOM. SET CIBP AT 3275' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1200', 750', AND 300'. RUN TUBING TO 1200' AND PUMP 35 SX'S COMMON WITH 3% CC AND 100# COTTON HULLS, PULL TUBING TO 750' AND WAIT 1 HOUR +. ATTEMPT TO TAG CEMENT-- APPEARED THAT DIDN'T. RUN TUBING BACK DOWN TO 1200' AND PUMP 35 MORE SX'S WITH 3% CC AND 100#S COTTON HULLS, GOT CEMENT RETURNS. PULL TUBING TO 750' AND PUMP 20 SX'S CEMENT WITH CC, PULL TUBING TO 300' AND CIRCUALTE 60-40 POZ, 4% GEL TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3328	3332		CSG

Remarks: L.K. WIRELINE #14414. QUALITY OILWELL CEMENT #1341.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

KCC WICHITA

APR 25 2016

RECEIVED

Form CP-2/3

NO 5-6-16

✓
JSC