

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-19203-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 2-21S-9W  
1670 feet from S Section Line, 1654 feet from E Section Line  
Lease Name: F SCHAFER Well #: 3  
County: RICE Total Vertical Depth: 3520 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: 234 W 11TH STE A PO BOX 70  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3415		125 SX
SURF	8.625	226		175 SX

Well Type: SWD UIC Docket No: D09515.0 Date/Time to Plug: 04/12/2016 11:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: AVEN WEVERLE Company: DAMAR RESOURCES, INC. Phone: (785) 623-3221

Proposed Plugging Method: AS ER KCC RULES & REGS. WELL HAD FAILED MIT. CP-1 INDICATES CASING LEAK AT 1330'.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/12/2016 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 750', AND 275'. RUN TUBING TO 3360' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC AND 200 #'S COTTON HULLS. PULL TUBING TO 1200' AND WAIT 1.5 HRS. TAGGED CEMENT @ 3408'. RUN TUBING BACK DOWN TO 3360' AND PUMP 35 SX'S COMMON WITH 3% CC & 100 #'S COTTON HULLS. FLUID STAYED AT SURFACE AND HAD CIRCULATION WHEN PUMPING. PULL TUBING UP TO 1390' AND PUMP 50 SX'S COMMON CEMENT WITH 2% CC & 100 #'S COTTON HULLS. PULL TUBING ON UP TO 750' AND PUMP 35 SX'S CEMENT, PULL TUBING ON UP TO 275' AND CIRCUALTE 60-40 POZ, 4% GEL TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3415	3520	OH	

Remarks: QUALITY OILWELL CEMENT TICKET #1338. L-K WIRELINE TICKET #13933. FAILED MIT

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

KCC WICHITA

APR 25 2016

RECEIVED

✓ SK

Form CP-2/3

MO 5-6-16  
cc UIC