

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21846-00-00
Spot: E2W2NW Sec/Twnshp/Rge: 28-11S-22W
3960 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BERENS RIES A Well #: 7
County: TREGO Total Vertical Depth: 3963 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4006		800 SX
SURF	8.625	210		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2016 8:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Alt I casing CWC with 800 sx cement.
Perforations: 3572' - 3575', 3592' - 3596', 3631' - 3633', 3649' - 3652', 3668' - 3671', 3691' - 3693'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2016 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3650' and pumped 20 sx neat cement followed by 55 sx cement w/200 # hulls.
Pulled tubing to 3200' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2200' and
pumped 75 sx cement. Good circulation of cement. Pulled tubing out. Squeezed casing with
15 sx cement. Shut in pressure 300 psi. Tied on to backside and squeezed with 5 sx cement.
Shut in pressure 300 psi.


GPS: 39.07006 -099.77478

Remarks: QUALITY CEMENT TICKET # 1952

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

Cm

APR 20 2016

Form CP-2/3

*70
5-6-16*