

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20589-00-00
Spot: W2E2NE Sec/Twnshp/Rge: 6-33S-16W
3998 feet from S Section Line, 1198 feet from E Section Line
Lease Name: MC ANINCH-GREGG Well #: 2
County: COMANCHE Total Vertical Depth: 5150 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 NW 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 2 SX CMT
PROD	4.5	5148	1718	WITH 150 SX CMT
SURF	8.625	428		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/30/2016 9:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: RICK POPP Company: CASTELLI EXPLORATION Phone: (620) 786-5514

Proposed Plugging Method: CIBP @ 5000' WITH 2 SX CMT. PLUG AT 950' WITH 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 30' WITH 15 SX CMT

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2016 11:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 966' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 467' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 15 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5070	5072		
5048	5061		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed E. M. R.
(TECHNICIAN)

RECEIVED
MAR 31 2016
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

APR 11 2016
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

NO
5-6-16