

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-24764-00-00  
Spot: NENENWNW Sec/Twnshp/Rge: 9-20S-21W  
5112 feet from S Section Line, 4179 feet from E Section Line  
Lease Name: BELTZ UNIT Well #: 1  
County: NESS Total Vertical Depth: 4510 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1501		
PROD	5.5	4507	1450	WITH 100 SX CMT
SURF	8.625	691		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2016 8:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: CODY Company: FRITZLER WELL SERVICE Phone: (785) 625-5155

Proposed Plugging Method: SAND BACK TO 4380' WITH 5 SX CMT. PLUG AT 1500' WITH 12 SX GEL & 50 SX CMT. PKUG AT 720' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/14/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SANDED BACK TO 4380' CAPPED WITH 5 SX CMT. 1ST PLUG AT 1450' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 338' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4432	4437		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed  (TECHNICIAN)

KCC WICHITA

APR 25 2016

RECEIVED

RECEIVED  
APR 21 2016  
KCC DODGE CITY

Form CP-2/3

no  
5-6-16  
KMS