

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-20618-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 25-23S-15W  
4771 feet from S Section Line, 1389 feet from E Section Line  
Lease Name: GUYER Well #: 2  
County: PAWNEE Total Vertical Depth: 3977 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3940	1597	WITH 100 SX CMT
SURF	8.625	256		WITH 210 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/12/2016 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SAND BACK TO 3750' WITH 4 SX CMT. PLUG AT 975' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/15/2016 9:30 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK TO 3750' & TOP WITH 4 SX CMT. TAGGED AT 3600'. 1ST PLUG AT 975' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3806	3812		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENTING.

Plugged through: CSG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED  
APR 21 2016  
KCC DODGE CITY

KCC WICHITA  
MAY 02 2016  
RECEIVED

Form CP-2/3

20  
5-6-16