

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-10034-00-01
Spot: NWNWSW Sec/Twnshp/Rge: 2-24S-21W
2301 feet from S Section Line, 4946 feet from E Section Line
Lease Name: REGNIER Well #: 2
County: HODGEMAN Total Vertical Depth: 2625 feet

Operator License No.: 31074
Op Name: BRAKE, JOE DBA BRAKE INC.
Address: RT 1 BOX 84
LATHAM, KS 67072

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	16	193		
PROD	4.5	2786	0	WITH 250 SX CMT
SURF	10.75	1426		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/05/2016 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: JOE BRAKE Company: JOE BRAKE INC Phone: (620) 965-2297

Proposed Plugging Method: RUN TBG TO 2600' & PUMP 20 SX CMT & 100# HULLS. PERFORATE AT 1450' & SPOT 50 SX CMT. PERFORATE AT 550' & CIRCULATE TO SURFACE INSIDE & OUT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 04/05/2016 3:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP BOTTOM WITH 20 SX GEL & 25 SX CMT & 200# HULLS. HELD PRESSURE AT 300 PSI. COULD NOT GET PAST 903' WITH PERF GUN. PERFORATED AT 903'. PUMPED 15 SX CMT. PERFORATED AT 550' & CIRCULATED UP 4 1/2" CASING WITH 48 SX CMT. SHUT IN. PUMPED 284 SX CMT ON BACKSIDE. HAD CIRCULATION BUT RAN OUT OF CMT. PULLED TBG. PUMPED 150 SX CMT WHICH CIRCULATED OUT 4 1/2" CASING. SHUT IN WITH 450 PSI.

Perfs:

Top	Bot	Thru	Comments
2506	2511		
2466	2471		
2457	2462		

KCC WICHITA
APR 18 2016
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed Larry Harris ECRS
(TECHNICIAN)
5A

RECEIVED
APR 12 2016
KCC DODGE CITY

Form CP-2/3
no
5-6-16