

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05478-00-01
Spot: SESESW Sec/Twnshp/Rge: 27-12S-16W
383 feet from S Section Line, 3056 feet from E Section Line
Lease Name: J I H FROELICH B Well #: 1
County: ELLIS Total Vertical Depth: 1005 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: PO BOX 329
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	1005		260 sx
PROD	5.5	3559		
SURF	8.625	200		125 sx

Well Type: SWD UIC Docket No: D19124.0 Date/Time to Plug: 04/12/2016 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE ROTH Company: EXPRESS WELL SERVICE Phone: (785) 623-3543

Proposed
Plugging
Method: Ordered 150 sx 6040 pozmix 4% gel cement with 400 # hulls.
4 1/2" Liner cemented in to surface from 1005' w/260 sx cement.
Perforations: CH 811' - 876'
Well Casing broke in at 750'
Emergency plug with rig over hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2016 12:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


Express Well Service ran in hole with tubing to 750'. Quality rigged to tubing and pumped 60 sx cement w/200 # hulls mixed in to circulate cement to pit area. Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sx cement w/500 psi. Shut in pressure 500 psi. Rigged to 8 5/8" surface casing with instant pressure of 300 psi.

Remarks: QUALITY CEMENTING CO TICKET # 1951

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

APR 13 2016

KCC WICHITA

Form CP-2/3

APR 19 2016

RECEIVED

Mo
5-6-16
CC WIC