

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21047-00-01
Spot: NESWSE Sec/Twnshp/Rge: 11-15S-29W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MALANCO Well #: 1
County: GOVE Total Vertical Depth: 4340 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4338		200 SX
SURF	8.625	393		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2016 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: CHEYENNE WELL SERVICE, INC. Phone: (620) 793-8186

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Shot perforations at 1965'.
Perforations: 3905' - 3907', 3923' - 3924', 3950' - 3953'.
CIBP at 3800'. Knocked out bridge plug.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2016 9:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3925' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2926' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 1960' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 960' and pumped 65 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 250 psi.

Perfs:


Top	Bot	Thru	Comments
3950	3953		
3923	3924		
3905	3907		

Remarks: CONSOLIDATED CEMENTING TICKET # 49666

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

KCC WICHITA

Form CP-2/3

APR 19 2016

RECEIVED

APR 08 2016

700
5-6-16