

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23369-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 31-16S-24W
2236 feet from S Section Line, 2296 feet from E Section Line
Lease Name: CURRY Well #: 1
County: NESS Total Vertical Depth: 4511 feet

Operator License No.: 33593
Op Name: BARRACUDA OPERATING COMPANY
Address: PO BOX 405
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4505	0	WITH 100 SX CMT
SURF	8.625	260		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2016 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BRIAN GABEL Company: BARRACUDA OPERATING Phone: (785) 798-3122

Proposed Plugging Method: JUNK IN HOLE AT 3500'. RUN TBG IN HOLE TO 3450' & PUMP 50 SX CMT & 100# HULLS. PULL TBG TO 1920' & CIRCULATE CM TO SURFACE WITH 200# HULLS. PULL TBG & TOP OFF. TIE ON & CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2016 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

TAG JUNK IN HOLE AT 3520'. RAN TBG TO 3500' & PUMP 50 SX CMT & 100# HULLS. PULL TBG TO 2000' & CIRCULATE CMT TO SURFACE. PULL TBG. TRIED TO TOP OFF WITH 20 SX CMT BUT WELL WENT ON VACUUM. SDON. 4/13/16: TAG CMT AT 350'. TOP OFF WITH 35 SX CMT. BACKSIDE TOOK 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4505	4511		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Larry Harris ECRS
(TECHNICIAN)

RECEIVED
APR 19 2016
KCC DODGE CITY

KCC WICHITA
APR 25 2016
RECEIVED

Form CP-2/3

no 5-6-16