

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-23458-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 31-16S-24W  
1594 feet from S Section Line, 1652 feet from E Section Line  
Lease Name: CURRY Well #: 3  
County: NESS Total Vertical Depth: 4514 feet

Operator License No.: 33593  
Op Name: BARRACUDA OPERATING COMPANY  
Address: PO BOX 405  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4505	0	WITH 150 SX CMT
SURF	8.625	252		WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/12/2016 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: BRIAN GABEL Company: BARRACUDA OPERATING Phone: (785) 731-5047

Proposed  
Plugging  
Method:

PUMP BOTTOM WITH 50 SX CMT & 100# HULLS TO 1915' & CIRCULATE CMT TO SURFACE. TIE ONTO BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2016 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

RAN TBG. PUMPED BOTTOM WITH 50 SX CMT & 100# HULLS. PULLED TO 2000' & PUMPED 225 SX CMT & 200# HULLS. NO CMT TO SURFACE. SDON. 4/13/16: TAG CMT AT 1070'. RAN TBG TO 1050' & CIRCULATED TO SURFACE WITH 115 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. FILLED ANNULUS WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4508	4514		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Larry Harris*

(TECHNICIAN)

KCC WICHITA SA

APR 25 2016

RECEIVED

RECEIVED  
APR 19 2016  
KCC DODGE CITY

Form CP-2/3

NO  
5-6-16