

2 090053

15-095-00457-00-02

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OWWOSE, SEC. 19, T. 28 S, R. 6 W/E XX feet from N/S section line feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171Lease Name Greenleaf Trust Well # OWWO #1Operator: TXO Production Corp.County Kingman 7150Name & Address 200 W. DouglasWell Total Depth 2200 feetWichita, Ks.Conductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 252'Abandoned Oil Well Gas Well Input Well SWD Well D&A ✓Other well as hereinafter indicated Plugging Contractor Kelson Casing & Pulling License Number 6050Address Chase, Ks.Company to plug at: Hour: 2:00 p.m. Day: 26 Month: 9 Year: 19 84Plugging proposal received from (company name) (phone) were: bottom plug; 35 sacks at 1800'top plug: 150 sacks 60-40 3%cc, 2% gel, 2 sacks hulls Plugging Proposal Received by David Wertz
(TECHNICIAN)Plugging Operations attended by Agent?: All Part X None Operations Completed: Hour: 1:00 Day: 28 Month: 9 Year: 19 84

ACTUAL PLUGGING REPORT The bottom was plugged by pumping 35 sacks of common, 3% cc to 1800'. There were no PIRTS to witness the bottom, on 9-26-84. We tried to pump down the 8 5/8 after running 3 hulls, 6 Gel. The cellar was full. Gel and hulls were coming up on the outside of the 8 5/8". On 9-28-84 we ran 2 3/8" tubing to 300', pumped two hulls and 150 sacks of 60-40 with 3%cc, 2% gel to surface.

RECEIVED
STATE CORPORATION COMMISSION

OCT 03 1984

10-03-84

CO. REGULATION DIVISION
WICHITA, KANSASRemarks: Sun Ticket #204482

(If additional description is necessary, use BACK of this form.)

INVOICED

(If ~~possible~~ observe this plugging.)DATE 10-8-84INV. NO. 4086

9-28

Signed David Wertz
(TECHNICIAN)

R0

FORM CP-2/3
Rev. 01-84