

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

01005-0001

API NUMBER: 15-095-30066-00-01

C/NW/NW, SECTION 20 TOWNSHIP 28 RANGE 6 W

OPERATOR LICENSE # 5399 4620 FEET FROM S SECTION LINE
OPERATOR American Energies Inc. 4620 FEET FROM E SECTION LINE
NAME & 155 N. Market ste 710
ADDRESS Wichita, Ks. 67202

LEASE NAME: Dye 2 132.08
COUNTY: KM
WELL TOTAL DEPTH: 4064
PIPE: 4.5 - 4064
SURFACE CASING: 8 5/8 267'

2/26

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DS&W Well Servicing
ADDRESS: P O Box 231 Claflin Ks. 67525 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 1:30 DAY: 26 MONTH: 2 YR: 2000

PLUGGING PROPOSAL RECEIVED FROM: Bryan
COMPANY NAME: DS & W Well Service PHONE: 316-587-3361
WERE: Sand to 3870 & 4 sacks
35 sacks at 1100'
35 sacks at 600'
300 to 0

RECEIVED
ST. CORPORATION COMMISSION

MAR 01 2000
03-01-00
Conservation Division
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED BY: JL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { X } PART { _____ } NONE { _____ }

COMPLETED: HOUR: 4:30P.M. DAY 26 MONTH: 2 YEAR: 2000

ACTUAL PLUGGING REPORT: Sanded bottom to 3870' & 4 sacks of common. Shot 4 1/2" casing off at 3000'. Pulled to 1100' pumped 35 sacks. Pulled to 650'. Pumped 35 sacks. Pulled to 300' circulated cement to surface.

REMARKS: Allied #3870 60/40 4%

INVOICED

DATE 3/1/00
WIZ. NO. 0.613360

I DID OBSERVE THIS PLUGGING.

[Signature]
JACK LUTHI

[Handwritten mark]