

2 050103

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,450 -00-00  
NW/4, SEC. 23, T. 28 S. R. 6 W/E  
660 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6762

Lease Name McHenry Well # 1-23

Operator: Mid-Kansas Exploration Co.

County Kingman

Name & Address 210 E. 6th

Well Total Depth 3945 <sup>128.22</sup> feet

South Hutchinson, Ks. 67501

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling License Number 5418

Address Box 1389 1105 Walnut Great Bend, Ks. 67530

Company to plug at: Hour: 12:00pm Day: 24th Month: April Year: 19 84

Plugging proposal received from Glenn Ward

(company name) Kansas Corporation Commission (K.C.C.) (phone) 262-8330

were: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:35pm Day: 24th Month: April Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with 11 barrells 36 viscosity mud; ran drill pipe

to 900', spotted 35 sx. cement through drill pipe. Pulled drill pipe to 240', spotted

35 sx. cement through drill pipe, pulled drill pipe. Pushed plug down to 40', filled

cement to surface. Ran one joint drill pipe in rat hole; circulated cement to surface

RECEIVED  
STATE CORPORATION COMMISSION

MAY 02 1984

Remarks: David Wertz attended plugging; Allied Ticket # 28566  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(If added/inserted) observe this plugging.

DATE 5-2-84

Signed Glenn Ward *Glenn Ward*  
(TECHNICIAN)

INV. NO. 1344

WK

FORM CP-2/3  
Rev. 01-84

4-24-84