

2-040776

9-22

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 207B
Wichita, Kansas 67202

API NUMBER: 15-095-20,150-0000

C SE NW, SECTION 25 TOWNSHIP 28 RANGE 6W

OPERATOR LICENSE # 5988

3300 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR HALLIBURTON OIL PROD CO
NAME & P O BOX 10
ADDRESS STAFFORD KS 67578 0010

LEASE NAME: HEDRICK #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4275' 138.93

PIPE: _____

SURFACE CASING: 8-5/8" @ 283'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: CHASE KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: RICHARD
COMPANY NAME: KELSO CASING PULLING PHONE: _____

WERE: 5-1/2" @ 4012' - PERFS 3884'-3894' - SAND TO 3834' & 5
SX - 35 SX @ 800' - CIRC FROM 330'

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: _____

OCT 17 1994

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____) CONSERVATION DIVISION
WICHITA, KS

COMPLETED: HOUR: _____ DAY: 22 MONTH: 9 YEAR: 1994

ACTUAL PLUGGING REPORT:

PERFS COVERED W/SAND FROM 4275'-3809' AND CAPPED W/5
SX CMT - 5-1/2" RECOVERED FROM 3016' & PULLED TO 803'
WHERE 35 SX CMT SPOTTED - 5-1/2" PULLED TO 330' WHERE
CMT WAS CIRC TO SURF - REMAINING PIPE PULLED AND TOPPED
OFF W/CMT

REMARKS: ALLIED 60/40 4%

INVOICED

DID OBSERVE THIS PLUGGING.

DATE OCT 18 1994

Steve Van Gieson (AGENT)

INV. NO. 41449