

12-13

RECEIVED
KANSAS CORPORATION COMMISSION

2-040-786

P

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

DEC 30 1994

CONSERVATION DIVISION
WICHITA, KS
API NUMBER: 15-077-20,919

095-20451-0000

C NE SW, SECTION 36 TOWNSHIP 28 RANGE 6W

OPERATOR LICENSE # 5428
5429 1980 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR GRAVES DRILLING CO INC
NAME & P O BOX 8250
ADDRESS WICHITA KS 67208

LEASE NAME: VICTOR #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 3933'

127.82

PIPE: 4-1/2" @ 3919'

SURFACE CASING: 8-5/8" @ 212'

ABANDONED OIL WELL GAS WELL INPUT WELL SUD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION
ADDRESS: MEDICINE LODGE KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: MARK MORGANSTEN
COMPANY NAME: CLARKE CORPORATION PHONE: 316-

WERE: OH 3919'-3933' - SAND TO 3870' & 4 SX - 35 SX 800' -
CIRC 400'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1200 DAY: 13 MONTH: 12 YEAR: 1994

ACTUAL PLUGGING REPORT:

OPEN HOLE WAS FILLED W/SAND TO 3870' & CAPPED W/4 SX
CMT - 4-1/2" WAS RECOVERED FROM 1950' & PULLED TO 801'
& 35 SX CMT SPOTTED - PIPE PULLED TO 317' & CMT CIRC TO
SURFACE

REMARKS: ALLIED 60/40 4% GEL

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE 1-6-95

INV. NO. 42007

12-13

Steve Van Bieson (AGENT)