

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2- 010187

1-9

API No. 15-095-19005 0001

API NUMBER: Drilled 6-61 #D-09.113

SE-SE SECTION 22 TOWNSHIP 28S RANGE 7W

OPERATOR LICENSE # 3880
OPERATOR K.C. Resources Inc.
NAME P.O. Box 1118
ADDRESS Cardiff, CA 92007

660 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

LEASE NAME: J.S. Gurtner #1

COUNTY Kingman

WELL TOTAL DEPTH: 4775'

155.19

PIPE:

SURFACE CASING 8 5/8" at 273'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD X D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Klima Well Service Inc.

ADDRESS: 610 Front St. Claflin, KS 67525 LICENSE: #7023

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 7 MONTH: 1 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Rod Hovland

COMPANY NAME: K.C. Resources Inc. PHONE: 405-769-0040

WERE: Sand to 4260' and top with 5 sxs cmt. Shoot pipe off and pull same. Pull pipe to 1125' and spot 35 sxs cmt. Pull pipe to 725' and spot 35 sxs cmt. Pull pipe to 325' and circulate cmt to the surface.

5 1/2" casing at 4500'

Perforations at 4360' to 4402'

Open hole from 4500' to 4775'

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 14:00 DAY: 9 MONTH: 1 YEAR: 1999

RECEIVED

KANSAS CORPORATION COMMISSION

ACTUAL PLUGGING REPORT: _____

FEB 03 1999

** SEE REVERSE SIDE **

2-3-99
CONSERVATION DIVISION
WICHITA, KS

REMARKS: Used a total of 492 sxs of 60/40 pozmix w/4% gel with various additives by United. Invoice #5008, #5009, and # 5010. (See reverse side for description of plugs).

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
Michael R. Wilson

FORM CP-2/3
REV. 3/90

INVOICED

DATE 2-9-99

INV. NO. 40618

ACTUAL PLUGGING REPORT

When pulling 2 3/8" tubing it parted at 917.25'. Ran 2 3/8" tubing with a spear and grapple to 240' and grabbed 3 1/2" liner. Pulled 683' (30 joints) of liner and the top section of the isolation packer. Reran tubing with spear and grapple to 923' and tried to grab remaining fish but could not retrieve any more liner. Pulled fishing tools and tubing. Ran 2 3/8" tubing to 902'. Annulus and tubing was on a vacuum. 1st plug-spotted 150 sxs cmt through tubing, pulled tubing to 500', and waited. Ran tubing to 922' and tagged fish-no fill but vacuum had decreased significantly. Ran tubing to 868'. 2nd plug-spotted 50 sxs cmt through tubing, pulled tubing to 500', and waited. Ran tubing to 875' and tagged cmt-no vacuum on annulus or tubing. Pulled tubing, ran in hole with C.I.B.P., and sat C.I.B.P. at 720'. Ran in hole with shot charge and perforated casing at 715' (2 shots). Ran tubing to 712'. 3rd plug-spotted 50 sxs cmt through tubing, pulled tubing to 400', and waited. Ran wireline to 720'-no cmt. Reran tubing to 712'. 4th plug-spotted 50 sxs cmt through tubing, pulled tubing to 400', and waited. Ran wireline to 718' and tagged cmt. Ran tubing to 652'. 5th plug-spotted 50 sxs cmt through tubing, pulled tubing to 212', and waited. Ran wireline to 675' and tagged cmt. Ran tubing to 560' and circulated 9 barrels gel spacer to the surface. Pulled tubing to 312'. 6th plug-circulated 127 sxs cmt to the surface, pulled all tubing, and topped off cmt with 15 sxs cmt. Top plug checked at 08:30 on 01/11/99 and cmt had dropped 17'-operator will top off.

PLUGS

1. 150 sxs of 60/40 pozmix w/4% gel, 5 lbs. gilsonite/sx, 1/4 lb. flo-seal/sx, and 100 lbs. hulls. Invoice #5008;
2. 50 sxs of 60/40 pozmix w/4% gel, 5 lbs. gilsonite/sx, 1/4 lb. flo-seal/sx, and 50 lbs. hulls. Invoice #5009;
3. 50 sxs of 60/40 pozmix w/4% gel, 5 lbs. gilsonite/sx, 1/4 lb. flo-seal/sx, and 50 lbs. hulls. Invoice #5009;
4. 50 sxs of 60/40 pozmix w/4% gel, 5 lbs. gilsonite/sx, 1/4 lb. flo-seal/sx, and 50 lbs. hulls. Invoice #5009;
5. 50 sxs of 60/40 pozmix w/4% gel, 5 lbs gilsonite/sx, 1/4 lb. flo-seal/sx, and 50 lbs. hulls. Invoice #5010;
6. 142 sxs of 60/40 pozmix w/4% gel. Invoice #5010.

Used 350 lbs. hulls, 1750 lbs. Gilsonite, and 87 1/2 lbs. flo-seal.

000000

000000

000000