

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1988

11-30-88

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-095-21,514 -0000

(of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

6/89

LEASE OPERATOR TXO PRODUCTION CORP. OPERATORS LICENSE NO. 5171

ADDRESS 1660 Lincoln St., Suite 1800 ^{Denver, CO} 80264 PHONE # (303) 861-4246

LEASE (EARM) Reida WELL NO. 2 WELL LOCATION C SW/4 COUNTY Kingman

SEC. 19 TWP. 28S RGE. 6 (E) or (W) TOTAL DEPTH 2180' PLUG BACK TD 2115'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 248 CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 2168 CEMENTED WITH 150 SACKS

PERFORATED AT 2046'-58', 4 JSPF (Indian Cave)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 175 gals sand dn csg., dump bail 4 sxs

cmt. Recover + 1200' 4 1/2" csg. Plug surface w/4 sxs hulls, 25 sxs 60-40 poz-mix 2% gel

2% cc, 10 sxs gel, 1 sx hulls, plug, 75 sxs 60-40 poz-mix 2% gel 2% cc.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? - IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be coordinated between TXO and KCC Field offices

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon Roberson

PHONE # (316) 886-5606

ADDRESS P.O. Box 125B Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Clarke Corporation

LICENSE NO. 5105 6/89

ADDRESS 107 W. Fowler, Box 187 Medicine Lodge, KS

PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED:

Ray West
(Operator or Agent)

DATE:

November 23, 1988

2



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

FEB 30 1989

EXPIRES

November 30, 1988
WELL PLUGGING NOTICE

Reida #2
C SW/4
Sec. 19-28S-06W
Kingman County

TXO Production Corporation
1660 Lincoln St., Ste. 1800
Denver, CO 80264

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #2 202 W. First, Ste. 300, Wichita, KS 67202 (316) 263-8809