

15-095-202610000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Maurice L Brown

Complete Address 1500 Vickers KSB&T Bldg. Wichita, Ks

Lease Name Turner Well No. 3

Location NE/SW/SE Sec. 10 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 3808

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 2:00 PM Day 23 Month 6 Year 1972

The above well was plugged as follows:

248 ft 8 5/8 surface pipe cemented with 225 sacks. 3882 ft 5 1/2 long
string cemented with 125 sacks. Open hole. Sand back to 3500 ft,
5 sacks cement with bailer. Pulled 2900 ft 5 1/2. Set 10 ft rock bridge
at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Russell Bihirstein
Well Plugging Supervisor

INVOICED

DATE 5/26/72

INV. NO. 5752-U