

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 20 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dunbar Drilling, Inc. 15-155-2045-0000

Complete Address 5252 North Broadway, Wichita, Kansas 67219

Lease Name Pierce Well No. 4

Location C N/2 NE NE Sec. 33 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 3342'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Operator

Address        License No. 709

Operation Completed: Hour 7 PM Day 3 Month January Year 1975

The above well was plugged as follows:

Hole filled with sand to 3300' and cemented with 5 sacks cement.

Rock bridge set from 555' to 545' and cemented with 10 sacks cement.

Rock bridge set from 217' to 200' and hole cemented with 50 sacks

cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30'

and hole cemented to base of cellar with 15 sacks cement.

10-3/4" conductor string set at 217' with 250 sacks cement.

1300' of 5 1/2" casing recovered.

389' of 8-5/8" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: *William D. Thomas*  
Well Plugging Supervisor

INVOICED

DATE 1/22/75

INV. NO. 675-W