

15095-30010-0000

FORM - CP-2
Rev. 9-8-64

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
FEB 26 1935
2. 26. 65
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Danny Biggs of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Biggs guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Yoeman Well No. # 1

Location: C NE NE Sec. 8 Twp. 28 Rge. 7 (E) (W) W

County Kingman Total Depth 4330' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Biggs was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 160 sacks.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent