

15-095-30010-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1965
2-26-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Yoeman Well No. # 1

Location C NE NE Sec. 8 Twp. 28 Rge. 7 (E) (W) W

County Kingman Total Depth 4330'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 5:45AM Day 25th Month Feb. Year 1965

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated with 160 sacks. Hole
was filled with drilling mud to 240', 1st cementing plug bridged
solid with dry cement and hulls on fluid at 240', and cemented with
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 2/26/65

INV. NO. 1734-u

Signed: Archie Elving
Well Plugging Supervisor