

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 095 - 20594 - 0000 (of this well)

Operator's Full Name Mac Oil Co.

Complete Address Box 400, Duncan, Okla. 73533

Lease Name Sparks Well No. 1

Location SE SW Sec. 10 Twp 28s Rge. 7 (E) (W) X

County Kingman Total Depth 4400

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kalso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 5 Pm. Day 3 Month 10 Year 1980

The above well was plugged as follows:

226' 8 5/8" casing, 4 1/2" casing set at 4069' w/150 sax cement-Plug
back to 4008'-Preforated at 3940' to 3950'-Allied mixed & pumped in
4 1/2" casing 50 sax common cement to 3750'-(Gas coming out of mandrel
on 8 5/8" casing) Pull 3390' casing. Howco mixed & pumped in 8 5/8"
casing 8 sax hulls-25 sax gel-150 sax 50/50 posmix cement w/4% gel
& 3% cc to top of casing. Shut in w/150# pressure.

RECEIVED
STATE CORPORATION COMMISSION

OCT - 6 1980
10-6-80
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10-10-80

INV. NO. 3300-w