

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 095-20599-0000 (of this well)

Operator's Full Name Mack Oil Co.

Complete Address Box 400, Duncan, Okla. 73533

Lease Name Rich Well No. 1

Location C NW Sec 15 Twp 28S Rge. 7 (E) (W) X

County Kingman Total Depth 4432

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:30 Am. Day 25 Month 8 Year 1980

The above well was plugged as follows:

279' 8 5/8" casing. 4 1/2" casing set at 4134' w/150 sax cement. Plug
back to 4090'-Pref's at 3969' to 74-Allied mixed & Pumped 35 sax
common cement in 4 1/2" casing-Topped at 3600'-PulI 3245' casing.
Allied Mixed & pumped in 8 5/8" casing 8 sax hulls-25 sax gel-
125 sax 50/50 posmix cement w/4% gel & 3% cc to top of casing.
Shut in w/600# pressure.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 8-28-80
INV. NO. 2983W

AUG 27 1980
8-27-80
CONSERVATION DIVISION
Wichita, Kansas