

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20635-0000 ✓

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name F.G. Holl

Complete Address 6427 E. Kellogg, Wichita, KS 67207

Lease Name Aldrich Well No. 44

Location SE SE SW Sec. 4 Twp. 24 Rge. 17W (East) (West)

County EDWARDS Total Depth 4440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4:30PM Day: 26 Month: 8 Year: 19 81

Plugging Operations attended by Agent? All xx Part None

The above well was plugged as follows:

Recovered 3005' of 4 1/2" csg. SIP 200#

260' of 8 5/8" SP W/225 sks. 4 1/2" set @ 4434' W/175 sks

PB to 4360' Perfs 4344' to 4350' SB to 4300' & W/4 sks

Pump 15 gel 6 hulls 10 gel, release plug and displace W/125 sks 50/50

pozmix 4% gel 3% C.C. Cemented by Allied

9-2-81

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 9-25-81

REV. NO. 7438W