

15-095-30013-0000

Form CP-3  
Rev. 6-26-62

*FP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 9 1965  
4-9-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name High Plains Production Company

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name Bolinger Well No. # 1

Location App. C NE SW Sec. 28 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Gabbert-Jones Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 12:30PM Day 8th Month April Year 1965

The Above well was plugged as follows:

208' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole  
was filled with drilling mud to 210', 1st cementing plug, bridged  
solid with dry cement and hulls on fluid at 210', and cemented with  
25 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged solid with dry cement and hulls on fluid at 40', and  
cemented with 10 sacks to the base of the cellar. Rat hole bridged .  
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

D E 4/9/65  
INV. NO. 953-W