

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155-20,797-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Woco, Inc.

Complete Address 2225 E. 21st. St., Suite 205, Wichita, Kansas

Lease Name Pierce Well No. 6

Location App. SE SE NE Sec. 33 Twp. 23 Rge. 4 (~~EAST~~) (West)

County Renov Total Depth 376'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated Lost Hole

Plugging Contractor Rosencrantz-Bemis Drilling Co and Halliburton Co.

Address Box 713, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 12:15 PM Day: 24 Month: November Year: 1981

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

Left in hole 351' of drill pipe - 93' of 2 1/2" Tubing 16' of 48" conduit  
Could not recover drill pipe. Washed down to 116' w/ 2 1/2" Tubing -  
Pumped 50 sacks cement through tubing at 116'. Pulled 1 Joint of  
Tubing. Pumped 150 sacks cement through tubing at 85' Top  
of cement at 42' in tubing. cement at 20' in hole. Pumped  
hole down and cemented 48" conduit too 4' of ground level  
with 7 yards ready-mix concrete.

RECEIVED 12-1-81  
STATE CORPORATION COMMISSION

DEC - 1 1981

I hereby certify that the above plugging instructions as herein stated.

**INVOICED**

DATE 12-21-81

INV. NO. 5822-U

Signed: [Signature]  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas