


15-155-20065-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Fred Shaffer

Complete Address: Wolcott Bldg., Hutchinson, Kansas 67501

Lease Name Rawlings Well No. 1

Location NE NE NW Sec. 33 Twp. 23 Rge. 4 (E) (W) X

County Reno Total Depth 1790'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Co., Inc.

Address: P.O. Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 6 PM Day 17 Month October Year 1968

The Above well was plugged as follows:

Hole filled with sand to 1700' and cemented with 3 sacks.

Rock bridge set from 250' to 240'. 5 sacks cement dumped on bridge and left to set


up. Hole bailed to 225' and cemented with 20 sacks (total 25 sacks). Hole filled

with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar

with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:   
Well Plugging Supervisor

DATE 10/22/68  
INV. NO. 8670-11