

15-095-01549-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 5 1965
10-5-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lario Oil & Gas Company
Complete Address: 301 S. Market, Wichita, Kansas
Lease Name Beck Well No. # 2
Location SW SE NE Sec. 29 Twp. 28 Rge. 5 (E) (W) W
County Kingman Total Depth 3950'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Glen & Smith Casing Pulling Company
Address: Box 156, Ellinwood, Kansas License No. 396
Operation Completed: Hour 11:30AM Day 4th Month Oct. Year 1965

The Above well was plugged as follows:

285' of 10 3/4" surface pipe, cement circulated. 3949' of 7" long string,
cemented with 100 sacks. Temperature survey 3550'. Plug back to 3900'. Top
perferation 3884'. Bottom of the hole was sanded to 3875', and cemented
with 5 sacks. 2500' of 7" long string was recovered from the hole. Fluid
in the hole was at 300', bridge plug and rock bridge from 300' to 290',
and cemented with 30 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/6/65
INV. NO. 1931-W