

1509501321-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 16 1963
 12-16-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. H. H. Stanley of Earl F. Wakefield has this date requested permission to plug the following described well:

Mr. Stanley guarantees payment of the plugging fee.

Operator's full Name: Earl F. Wakefield

Complete Address: 515 Union Center, Wichita, Kansas

Lease Name: Bolinger "A" Well No. # 1

Location: C NE NW Sec. 28 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 3900 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stanley was instructed to plug the well as follows:

149' of 8 5/8" surface pipe, cemented with 100 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, cement with 30 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent