

15-09579140-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1964
10-12-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

10-6-64

Dear Sir:

Mr. W. Voth of Knight Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Drillers Drilling Production Company

Complete Address: 1020 Union National Building, Wichita, KANSAS

Lease Name: Kostner Well No. #3

Location: G-SW-NE Sec. 30 Twp. 28 Rge. 5 (E) (W) W

County Kingman Total Depth 3955 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. W. Voth was instructed to plug the well as follows:

268 feet of 8 5/8" Surface Pipe circulated with cement. 3955 feet of
5 1/2" Long String cemented with 20 sacks. Perforated at 3904, sanded
to 3900 and cemented with 3 sacks. Mud to 275 feet, 10 feet Rock Bridge cemented
with 25 sacks. Mud to 40 feet, 10 feet Rock Bridge cemented with 10 sacks
to bottom of cellar.

Very truly yours,

Robertson Justice
Conservation Division Agent