



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 3, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Charles D. Johnson

Complete Address: P.O. Box 231, Mc Pherson, Kansas 67460

Lease Name: Goering Well No. 1-A

Location: SE SW SE Sec. 33 Twp. 23 Rge. 4 (E)(W) X

County: Reno Total Depth 3385' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/2 sack hulls to 250' and
cement hole with 35 sacks through drill pipe. Fill hole with mud
to 30'. Push plug and 1/2 sack hulls to 30' and cap hole with 15 sacks
cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

Conservation Division Agent