



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg.  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

October 14, 1968

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clerk of Southwest Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Fred Shaffer

Complete Address: Wolcott Bldg., Hutchinson, Kansas 67501

Lease Name: Rawlings Well No. 1

Location: NE NE NW Sec. 33 Twp. 23 Rge. 4  (E)  (W)  X

County: Reno Total Depth 1790' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Clark was instructed to plug the well as follows:

Fill hole with sand to 1700' and cement with 3 sacks.

Set rock bridge from 250' to 240'. Dump 5 sacks cement on bridge and

let set up. Bail hole to 225' and cement hole with 20 sacks (total 25

sacks). Fill hole with mud to 40'. Set rock bridge from 40' to 30'

and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent