



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1962

CONSERVATION DIVISION  
Wichita, Kansas

10-1-62

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date Sept. 21, 1962., 1962, authorized  
the following plugging operation:

Operator's full Name: Morgenstern Oil Operations.

Complete Address: Box 2562 Wichita, Kansas.

Lease Name: Casley #4 Well No. #4

Location: NE SW NW Sec. 11 Twp. 28 Rge. 5 (E) (W) X

County Kingman. Total Depth 3802'

Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated: Abandoned Oil Well.

Operator was instructed to plug well as follows:

3792' of 5 1/2" pipe. Hole sanded to 3785' & 5 sacks of  
cement with baler. 3430' of pipe pulled. 153' of 8 5/8"  
surface pipe circulated with 100 sacks cement. Hole filled  
to 150' with mud, 10' rock bridge and 25 sacks cement.  
Hole filled to 35' with mud, 10' rock bridge and 10 sacks  
cement to base of cellar.

Very truly yours,

*J. P. Roberts*  
Conservation Division Agent