

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-21,055-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Gear Petroleum Co. Inc.

Complete Address 300 Sutton Place Wichita Kansas 67202

Lease Name D. Britton Well No. 4650' 1-3

Location S⁵/₂ S¹/₂ - S¹/₂ - NW Sec. 3 Twp. 24 Rge. 18 (East) (West)

County Edwards Total Depth 4650

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co.

Address 1720 Kansas State Bank Bldg. Wichita Kans 67202 License No. _____

Operation Completed: Hour: 7:15 AM Day: 18 Month: July Year: 19 82

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

The anhydrite was topped at 1300'. 1st plug at 1280' with 40 sby of cement. 2nd plug at 520' with 40 sby of cement. 3rd plug on solid bridge at 40' to 0' with 10 sby of cement. Then circulated 10 sby of cement in rat hole. The cement was pumped through drill pipe with hole full of heavy mud. The cement used was 50/50 Pos 29 gell & 3% CC. The plugging was accomplished by allied cementing. The farmer is keeping water well.

Amount of Surface Casing: 474' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthin
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED Signed: _____
STATE CORPORATION COMMISSION Conservation Division Agent

JUL 20 1982

INVOICED

DATE 7-22-82

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 707-W