

15-095-00354-1001

Form CP-3  
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued August 3, 1967.

Operator's Full Name H. C. Bennett

Complete Address 1212 Union National Bldg., Wichita, Kansas 67202

Lease Name Lucy Stucky Well No. # 1

Location SE SE NW Sec. 1 Twp. 27 Rge. 8 (E) W

County Kingman Total Depth 4334'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Flint Engineering & Construction Company

Address Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:00 P.M. Day 11th Month August Year 1967

The above well was plugged as follows:

270' of 8 5/8" surface pipe, cemented with 275 sacks. 3710' of 5 1/2" long  
string, cemented with 100 sacks. Plug back T.D. 3676'. Top perforation 3412'.  
Bottom of the hole was sanded to 3400', and cemented with 5 sacks, through  
the dump bailer, with cement from 3400' to 3360'. 3220' of 5 1/2" long string  
was recovered from the hole. Hole was filled with mud to 260', rock bridge  
from 260' to 250', and cemented with 25 sacks, with cement from 250' to 175'.  
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented  
with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6131-W