


150950322-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN County. Sec. 29 Twp. 28s. Rge. 5w. (#) (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner PETROLEUM, INC.
Lease Name BOLINGER "B" Well No. 3
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 16 19 60
Application for plugging filed NOVEMBER 16 19 60
Application for plugging approved NOVEMBER 16 19 60
Plugging commenced NOVEMBER 16 19 60
Plugging completed NOVEMBER 16 19 60
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production --- 19 ---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED W. HAMPEL, PRETTY PRAIRIE, KANSAS
Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 3932 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from --- feet to --- feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 210' FOLLOWED BY A WOODEN PLUG AND 1/4 SACK OF HULLS.
PLACED 10 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF HULLS. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY A WOODEN PLUG AND 1/4 SACK OF HULLS, PLACED 10 SACKS OF CEMENT ON TOP OF HULLS TO BASE OF WELL CELLAR.

STATE OF KANSAS
COMMISSION
DEC 1 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of NOVEMBER, 19 60

Arthur J. Miles
Notary Public.

My commission expires APRIL 14, 1963



WELL LOG

15-09501322-0500

COMPANY PETROLEUM, INCORPORATED

SEC. 29 T28S R. 5W

FARM BOLINGER "B" NO. 3

LOC. SE, SW, NW


TOTAL DEPTH 3932'

COUNTY KINGMAN CO., KANSAS

COMM. November 7, 1960 COMP. November 16, 1960

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8 5/8" @ 219' w/150 sax.



ELEVATION 1445' DF'

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

60	Surface soil & sand
219	Red bed
785	Shale
960	Shale & shells
1245	Shale & lime
1580	Lime & shale
1825	Shale
2110	Shale & shells
2545	Shale & lime
3252	Lime & shale
3750	Lime
3840	Lime & shale
3932	Mississippi lime
3932	T. D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 1960
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #3 BOLINGER "B" well

Verne A. Morris

Subscribed and sworn to before me this 28th day of November 19 60

My Commission Expires: April 14, 1963

Arthur J. Miles
NOTARY PUBLIC