

15-095-30056-050

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

KINGMAN County. Sec. 11 Twp. 28s Rge. 5 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW
Lease Owner PETROLEUM, INC.
Lease Name BROWN "X" Well No. 1
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed DEC. 20 19 65
Application for plugging filed DEC. 20 19 65
Application for plugging approved DEC. 20 19 65
Plugging commenced DEC. 20 19 65
Plugging completed DEC. 20 19 65
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 200', SET BRIDGE AND PLACED 25 SACKS CEMENT ON TOP OF BRIDGE. MUDDED UP WITH HEAVY MUD TO 40', SET BRIDGE AND PLACED 10 SACKS CEMENT ON TOP OF BRIDGE TO BASE OF WELL CELLAR.

RECEIVED
CONSERVATION DIVISION
JAN 6 1966
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R. R. #2 GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 4 day of JANUARY, 19 66

My commission expires MAY 28, 1969 *Richard A. Dumas* Notary Public.

WELL LOG

15-095-30056-0000

COMPANY Petroleum, Inc.

SEC. 11 T. 28S R. 5W

FARM Brown

NO. 1-X

LOC. SW SW


TOTAL DEPTH 3885'

COUNTY Kingman

COMM. 12-10-65

COMP. 12-21-65

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 208' w/175 sx

ELEVATION 1406' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

128' Red Rock
 155' Red Bed and Shale
 705' Shale and Shells
 1215' Lime and Shale
 1470' Lime
 1650' Lime with Shale
 2255' Shale and Lime
 3184' Lime and Shale
 3235' Lime
 3320' Lime with Shale
 3417' Lime
 3445' Shale
 3635' Lime with Shale
 3700' Shale and Lime
 3785' Lime with Shale
 3800' Mississippi
 3820' Mississippi Chert
 3850' Mississippi
 3885' Mississippi Chat
 3885' RTD

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1966

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Brown 1-X well.

Sam N. Stephens

Subscribed and sworn to before me this 4th day of January 19 66

My Commission Expires: November 5, 1969

Richard L. Boyz
NOTARY PUBLIC