


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. ¹¹ 28 Twp. ²⁸ 11 Rge. (E) 5 (W)
Location as "NE/CNW/SW" or footage from lines Cr/2 NE NE
Lease Owner Pickrell Drilling Co. & Franco Central Oil Co.
Lease Name Casley A Well No. 1
Office Address 705 Fourth Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/27 1954
Application for plugging filed 11/27 1954
Application for plugging approved 11/27 1954
Plugging commenced 11/27 1954
Plugging completed 11/27 1954
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3826 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	160	8 5/8"	160'	No
No oil string was run.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 160', bridge hole and cement
with 20 sacks. Then heavy mud to 20' below cellar,
bridge hole and cement with 10 sacks to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner or owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
705 Fourth National Bank Bldg.
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 1954

[Signature] Notary Public.

My commission expires July 30, 1958

PLUGGING
FILE SEC 11 T 28 R 54
BOOK PAGE 80 LINE 21

12-01-54

ROTARY DRILLING LOG

15-095 01481-0000

COMPANY: Pickrell Drilling Company & Franco Central Oil Company, Wichita, Kansas

Rotary Drilling Commenced 11/17/54

Rotary Drilling Completed 11/27/54

LOCATION: Casley A-1 CN/2 NE NE 11-28S-5W, Kingman County

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 4 Jts of 8 5/8" surface casing set at 160' with 125 sacks cement circulated
Hole filled with heavy mud to 160', bridge hole and cement with 20 sacks. Then heavy mud to 20' below cellar, bridge hole and cement with 10 sacks to bottom of cellar.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Sand	50	Circ. for samples @	3747
Red Rock & shale	160	" " "	" 3756
Shale	430	" " "	" 3780
Salt Shale & Shells	830	" " "	" 3791
Shale & lime	1675	" " "	" 3795
Shale	1915	" " "	" 3802
Shale & shells	2115	" " "	" 3810
Shale & lime	2710	" " "	" 3820
Lime	3780		
Mississippi	3826	RTD	

S.L.M. at 3000 - O.K.
S.L.M. at 3826 - O.K.

Slope Test at 3000 - 0° off
Slope Test at 3826 - 0° off

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebitts*
Attorney-in-Fact

STATE OF KANSAS, }
COUNTY OF SEDGWICK } ss.:

On this 30th day of November, 1954, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

PLUGGING
FILE SEC 11 T 28 R 54
BOOK PAGE 10 LINE 21

Notary Public