


15-095-21016-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plot

Kingman County, Sec. 15 Twp. 28S Rge. 5W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines C-NW SW SE

Lease Owner Vincent Oil Corporation
Lease Name Lindholm Well No. 1
Office Address 230 O.W. Garvey Bldg., 200 W. Douglas,
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Wichita, KS 67202
Date Well completed November 15, 1980
Application for plugging filed verbal Application 1980
Application for plugging approved Verbal Approval 1980
Plugging commenced November 15, 1980
Plugging completed 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,890'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	312'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,890 ft. (rotary total depth) to 320 ft. Set plug at 320 ft. and cemented with 30 sacks cement. Filled hole with heavy rotary mud from 320 ft. to 160 ft. Set plug at 160 ft. and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 160 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~Employee of owner~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water #10, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of November, 1980

My commission expires July 25, 1982

Elsie Willison
Notary Public

STATE RECEIVED
NOV 19 1980
CONSERVATION DIVISION
Wichita, Kansas

11-19-80

