

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kingman County. Sec. 15 Twp. 28S Rge. 5 (X) (W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Lindholm Well No. 1
Office Address 706 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 20 19 64
Application for plugging filed June 20 19 64
Application for plugging approved June 20 19 64
Plugging commenced June 20 19 64
Plugging completed June 20 19 64
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 3875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 230' with heavy mud
Set plug @ 230' with 25 sacks cement
Filled hole to 40' with heavy mud
Set plug @ 40' with 10 sacks cement to bottom of celler
Used 2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

De-26-64 JUN 26 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Thunderbird Drilling, Inc.
Address 706 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Charles W. Aikins, Jr. (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Aikins, Jr., President
706 Union Center (Address) Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 24th day of June, 19 64

My commission expires October 9, 1967

Priscilla L. Graham
Priscilla L. Graham Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

15-095-00485-000
JUN 26 1964

DRILLERS LOG

#1 Lindholm

CONSERVATION DIVISION
Wichita, Kansas

LOCATION: C NE SE of Section 15,
Township 28 South, Range 5 West,
Kingman County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
706 Union Center Building
Wichita, Kansas

COMMENCED: June 9, 1964

COMPLETED: June 20, 1964

SURFACE CASING: 8-5/8" surface casing set at 233'
with 200 sacks cement, 1% gel,
3 sacks calcium chloride, 2 sacks
ammonia chloride.

ELEVATION: 1394' K. B.
1391' D. F.
1389' G. L.

WELL LOG:

0 - 40	Red Bed
40 - 700	Red Bed & Shale
700 - 1060	Shale & Lime
1060 - 1480	Lime & Shale
1480 - 1610	Shale & Lime
1610 - 1735	Lime & Shale
1735 - 3290	Shale & Lime
3290 - 3475	Lime
3475 - 3796	Shale & Lime
3796 - 3820	Cherty Lime
3820 - 3875	Lime
3875	Rotary Total Depth D & A

The undersigned, Charles W. Aikins, Jr., an officer of
Thunderbird Drilling, Inc., hereby certifies that the above is a true and
correct log of the formations encountered in the drilling of the #1 Lindholm
as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.


Charles W. Aikins, Jr., President

Subscribed and sworn to before me this 25th day of June, 1964.


Priscilla L. Graham, Notary Public

My commission expires 10-9-67.